

Volume Report
Subgrade vs. Existing

	Total	Cut	Area		Volume		Comp/Ratio		Compact		Export -Import	Change Per .1 Ft
			Fill	OnGrade	Cut	Fill	Cut	Fill	Cut	Fill		
K-5 Sand	4,470	4,470	0	0	232	0	1.00	1.15	232	0	232	19
K-5 Sand	4,471	4,471	0	0	248	0	1.00	1.15	248	0	248	19
K Sub:	8,941	8,941	0	0	480	0			480	0	480	38
Pad Island	43,268	0	43,267	1	0	11,517	1.00	1.15	0	13,245	-13,245	184
Porous Paving	12,663	40	12,307	316	0	964	1.00	1.15	0	1,109	-1,109	54
Porous Paving	1,086	76	351	659	1	5	1.00	1.15	1	6	-5	5
Porous Paving	13,766	0	13,766	0	0	1,855	1.00	1.15	0	2,133	-2,133	59
Porous Paving	5,019	0	5,019	0	0	1,245	1.00	1.15	0	1,432	-1,432	21
Porous Sub:	32,534	116	31,443	975	1	4,069			1	4,680	-4,679	139
Standard Paving	166,637	1,148	165,323	166	28	28,159	1.00	1.15	28	32,383	-32,355	710
Regions Total	251,380	10,205	240,033	1,142	509	43,745			509	50,308	-49,799	1,071
Unspecified	151,075	85,586	58,142	7,347	13,995	4,982	1.00	1.15	13,995	5,729	8,266	643
Job Total	402,455	95,791	298,175	8,489	14,504	48,727			14,504	56,037	-41,533	1,714

Sectional Qtys	Plane Area	Slope Area	Depth	Volume
Grading	151,075	154,155	0.330	1,884
K-5 Sand	4,470	4,470	0.500	83
K-5 Sand	4,471	4,471	0.500	83
K Sub:	8,941	8,941		166
Pad Island	43,268	43,268	0.670	1,074
Porous Paving	5,019	5,030	1.500	279
Porous Paving	1,086	1,086	1.500	60
Porous Paving	12,663	12,711	1.500	706
Porous Paving	13,766	13,772	1.500	765
Porous Sub:	32,534	32,599		1,810
Standard Paving	166,637	166,735	1.000	6,175
Sectional Total	402,455	405,698		11,109